BANGALORE SANITARY RANGE.

Dated 29th July 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Bangalore Sanitary Range, up to 4 P. M., 20th August 1904, for the construction of drains in the conservancy lanes at Chamarajendrapet, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1905.

2. The plans, detailed estimate, specifications and conditions may be seen at the Assistant Engineer's office at Chamarajendrapet between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains in the conservancy lanes at Chamarajendrapet, Bangalore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of estimate for constructing drains in the conservancy lanes at Chamarajendrapet, Bangalore City:

Items of work.		
I. Excavation of trench in all soils	C. yds.	2,038
II. Surki concrete as per specification or burnt brick in surki mortar.	C. ft.	36,411
III. Burnt stone slabs for coping including dressing and fixing in mortar.	S. ft.	30,091
IV. Plastering with cement	Sqrs.	534·56
V. House connections	No.	2,204
VI. Forming lanes	S. yds.	25,000
VII. Blasting Rock	Lump sum.	

R. V. SUNDARAMIAR, *Asst. Engineer.*

KOLAR DIVISION.

Notice dated 6th August 1904.

A sum of (Rs. 23-11-0) rupees twenty-three and annas eleven only has been outstanding in the accounts of this Division since June 1901 against the name of deceased Task Work Contractor Abdul Aziz for work done, Annual Repairs of Kolar Gold Fields Railway feeder road. Persons claiming the said amount should appear before the Executive Engineer, Kolar Division, with necessary heirship certificate within thirty days from this date to receive payment of the said amount. Otherwise it will be forfeited to Government.

B. SUBBA RAO, *Executive Engineer.*

CHITALDRUG DIVISION.

Dated 30th July 1904.

Improving Dharmapur tank, Registered No. 129 of Hiriyur Taluk.

"Attention is invited to advertisement in the *Mysore Gazette*, dated 4th August 1904, calling for tenders for the above work."

Dated 10th August 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 3rd September 1904. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. to 5. P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Talya tank Registered No. 33 of Holalkere Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract showing the quantities of works to be done for Improving Talya Tank Registered No. 33 of Holalkere Taluk.

Items of work.	*Per.*	*Quantity.*
Bund 58·00 and top width 6'—		
Earth-work to bund, excavating, carrying, watering and tamping from pits in the bed of tank.	C. yd.	6,636
From the foundation of revetment	"	3,801
To be thrown as spoil earth	"	1,901
Gravel backing	"	5,612
New stone work	"	2,921
Old stone work	"	1,326
Refixing grade-stones	Each	40
New grade stones	"	11
B. M. Stones	"	2
Year stone	"	1
Registered number stone	"	1
Top width stones	"	51
Gauge stones	"	2
	L. S.	Rs.
Constructing steps		
Turfing	Sq. yd.	6,952
Excavating trench between grades 5 × 8½	L. S.	Rs.
Blocking up the left waste weir by a Masonry wall, left—		
Removing and refixing the present covering slab of the body wall.	L. S.	Rs.
Burnt brick in surki mortar	C. ft.	493
Plastering with surki mortar	Sqr.	5·00
Old stone work	C. yd.	63
Right (waste weir 130+26)=156 R. L. 52·00—		
	L. S.	Rs.
Repairing the existing apron		
Concrete	C. ft.	116
Burnt brick in surki mortar	"	1,475
Burnt stone slabs	S. ft.	381
Rough plastering	Sqr.	11·42
Fine plaster with surki mortar	"	4·00
	L. S.	Rs.
Removing the present rough stone wall		
Rough stone work, new	C. yd.	117

N. B.—Whole of the excavation C. yds. 1,158 to be charged to bund and gravel backing, hence no provision is made here for excavation.

Repairing or reconstructing sluice No. 2.—		
Earth-work excavation and refilling	C. yd.	423
Brick in surki mortar	C. ft.	1,300
Burnt stone slabs	S. ft.	330
Fine plaster with surki martar	Sqr.	3·27
Rough do	"	4·28
Gibbit stones	Each.	2
Cutting orifices	"	4
Sluice No. 1.—		
Reconstructing the front cistern and repairing and examining the sluice.	L. S.	Rs.

Y. SRINIVASA RAO, *Executive Engineer.*